Office of the Director of Boiler,Gujarat State

3rd Floor, D Block, Bahumali Bhawan,Manjushri Mill Compound, Asarva, Girdharnagar
Ahmedabad- 380004.
e-mail :- cisbnsn-lab-ahd@gujarat.gov.in & Web site :- http://www.boiler.gujarat.gov.in

No. DOB/TECH/2026/CA062026-20270002346 Date:29/06/2026

To,
AUTHORISED SIGNATORY
ASR MET TECH PVT LTD.,
SUEVEY NO.48, OPP. SUPER GAS, NR. MONGAL MATA MANDIR, TAL - BAVLA, KALYANGADH - 382220, DIST - AHMEDABAD, GUJARAT, INDIA,BAVLA,AHMEDABAD,382220

Sub : Extension of Approval of your workshop for Manufacturing of Stainless Steel / Duplex Steel Seamless Pipe/ Tube & U Tubes under inspection of IBR - 1950 Code.

Ref.:1 First Approval Letter No.A0032022-20230001627 Date. 28/06/2022

Sir,

With reference to above you subject & refered letter **the approval granted to your firm for "Manufacturing of Stainless Steel / Duplex Steel Seamless Pipe/ Tube & U Tubes"** under inspection of IBR -1950 is extended for **Two** years . i.e from **28/06/2026** to **27/06/2028** All other terms and conditions shall remain the same as per reference letter 1.

Workshop approval fees of Rs.10,000.00 has been received vide online receipt no 3290211, dtd.06/06/2026 Also, you are instructed to apply for renewal of firm recognition at least two months prior to the expiry of this validity.

Signature Not Verified
Digitally signed by BIPINKUMAR HIMMATLAL PATEL
Date: 2026.07.06 14:24:04 IST
Reason: Approval
Location: Gandhinagar

Shri B. H. Patel
Director of Boilers, Gujarat State

Copy to: D.O.B / TECH /2026 /CA062026-20270002346 29/06/2026 Dated
Shri A N Chudasama, Deputy Director of Boilers, Ahmedabad region for information and necessary action.

Annexure

1 Raw material for Pipes, Tubes & 'U' Tubes must be offered for inspection along with Certificate in Form III-A / III-B / IV of IBR – 1950 with mill test certificates if procured from Well Known Steel Pipe / Tube maker's as per IBR – 1950 before commencement of manufacturing.

2 Drawings of 'U' Tubes must be got approved from the under signed as per Regulation 395 of IBR – 1950 before starting manufacturing.

3 Physical / Mechanical tests and Eddy Current testing of Pipes, Tubes & 'U' Tubes must be done in presence of the Competent Person, in your In-house approved Laboratory. All machines must have valid calibration failing which testing will not be allowed in in-house laboratory.

4 Chemical tests of samples of Pipes, Tubes & 'U' Tubes must be done in presence of the Competent Person in the Laboratory approved by this office.

5 Other Non-Destructive tests like Micro, Macro, UT, IGC, MPI, PMI etc. of Pipes, Tubes & 'U' Tubes must be done as per the requirements of Material Specifications / IBR – 1950 in the Laboratory approved by this office or by recognized NDT Agency.

6 Construction and workmanship must be in accordance with the Indian Boiler Regulations – 1950 and to the satisfaction of the Competent Person or Inspecting Authority.

7 You shall have to carry out manufacturing of Pipes, Tubes & 'U' Tubes as per instructions issued from time to time either by Competent Person or Inspecting Authority.

8 This approval/ recognition can be withdrawn at any time without giving notice if the workmanship is not found satisfactory as per IBR – 1950.

9 You will have to inform this office immediately if there is any change in existing name of the Company / Existing Technical Staff of the Company.

10 You will have to employ sufficient technical staff to the satisfaction of the Inspecting Authority time to time.

11 You are hereby insutructed to get it renewed before 60 days from the expire of this certificate.

12 Other